

Date: Tuesday, 07/04/2009 10:20:45 AM  
 User: Julie Dawson

## Process Sheet

<b>Customer</b> :	CU-DAR001 Dart Helicopters Services	<b>Drawing Name</b> :	FLOOR PROTECTOR FWD RH
<b>Job Number</b> :	46976		
<b>Estimate Number</b> :	11234		
<b>P.O. Number</b> :		<b>Part Number</b> :	D32812
<b>This Issue</b> :	07/04/2009	<b>Drawing Number</b> :	D3281 REV. D
<b>Prsht Rev.</b> :	NC	<b>Project Number</b> :	N/A
<b>First Issue</b> :	//	<b>Drawing Revision</b> :	D
<b>Previous Run</b> :	44335	<b>Material</b> :	
<b>Written By</b> :		<b>Due Date</b> :	20/04/2009
<b>Checked &amp; Approved By</b> :	<u>JW 09.04.07</u>	<b>Qty:</b>	6
<b>Comment</b> :	Est Rev A 04.07.01 New issue KJ/JLM Est Rev B 07.08.07 Thermoform in house DL Est Rev C 08.02.06 To reflect updated dwg. DL Est. Rev D 08.04.15 Material Change DL		

## Additional Product

Job Number:



<b>Seq. #:</b>	<b>Machine Or Operation:</b>	<b>Description :</b>
----------------	------------------------------	----------------------

1.0	MLEXS093F600602	GE PLASTICS LEXAN SHEET
-----	-----------------	-------------------------



**Comment:** Qty.: 4.3330 sf(s)/Unit Total : 25.9980 sf(s)  
 GE PLASTICS LEXAN SHEET

Material Batch Number

M110877

BB 09/04/20

2.0	HAND FINISH TH	HAND FINISHING THERMOFORMING
-----	----------------	------------------------------

**Comment:** HAND FINISHING THERMOFORMING

1) Cut Blanks

BB 09/04/20 X6

3.0	THERMOFORMING	THERMOFORMING MACHINE
-----	---------------	-----------------------

**Comment:** THERMOFORMING MACHINE

Thermoform as per Dwg. D32811 and Folio FTA 008

Dwg. Rev.

Folio Rev.

D  
B

BB 09/04/20 X6

4.0	QC2	INSPECT PARTS AS THEY COME OFF MACHINE
-----	-----	--

**Comment:** INSPECT PARTS AS THEY COME OFF MACHINE

BB 09/04/20 X6

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector	

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries

Date: Tuesday, 07/04/2009 10:20:45 AM  
User: Julie Dawson

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: FLOOR PROTECTOR FWD RH

Job Number: 46976

Part Number: D32812

Job Number:



Seq. #: Machine Or Operation: Description :

5.0 HAND FINISH TH HAND FINISHING THERMOFORMING



Comment: HAND FINISHING THERMOFORMING

1) Trim to Finished Dimensions

BB 09/04/22 (X6)

6.0 QC2 INSPECT PARTS AS THEY COME OFF MACHINE



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

1) Check Surface finish for undesired marks, voids, dimples etc.

2) Check dimensions to ensure conformity to drawing tolerances.

BB 09/04/22 (X6)

7.0 QC5 INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

BB 09/04/22 (6)

8.0 PACKAGING 1 PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

PPP 46816

BB 09/04/22 (X6)

9.0 QC21 FINAL INSPECTION/W/O RELEASE



Comment: FINAL INSPECTION/W/O RELEASE

09/04/23

Job Completion



u 09/04/23

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector	

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

Resolution: \_\_\_\_\_ Disposition: \_\_\_\_\_ QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries

<b>DART AEROSPACE LTD</b>		<b>Work Order:</b> 46970
<b>Description:</b> Floor Protector, Fwd RH		<b>Part Number:</b> D3281-2
<b>Inspection Dwg:</b> D3281	<b>Rev:</b> D	<b>Page 1 of 1</b>

### FIRST ARTICLE INSPECTION CHECKLIST

☒ First Article ☐ Prototype

#### THERMOFORMING SECTION

Description	Accept	Reject	Method of Inspection	Comments
Inside Radii less than 0.1875" Go/No Go	✓			
Shape Definition	✓			
Texture Retention	✓			
Material imperfections such as bumps, cracks, voids, scratching	✓			

Measured by: BB Date: 09/04/21

#### TRIMMING SECTION


Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
18.3	+/-0.100	18.3	✓			
17.4	+/-0.100	17.375	✓			
12.1	+/-0.100	12	✓			
0.95	+/-0.030	.985	✓			
0.25	+/-0.030	.264	✓			
0.030	Min	.058	✓			
0.070	Min	.077	✓			

Measured by: BB Date: 09/04/21

Audited by: th Date: 09/04/21

Prototype Approval: N/A Date: N/A

Rev	Date	Change	Revised by	Approved
A	08.02.28	New Issue	KJ/DL	
B	08.04.16	Dimensions updated per Dwg Rev D	KJ/DL	
C	08.07.23	Dwg Rev updated	KJ/DL	
D	08.09.12	Tolerance revised for 0.070 dimension	KJ/DL	th






**D3281-1 FLOOR PROTECTOR**

**D3281-1 NOTES:**

- 1) THERMOFORM WITH MOLD D3281-1T1 PER DART QSI 022; TRIM AS SHOWN  
MINIMUM THICKNESS AFTER FORMING: 0.070" EXCEPT WHERE INDICATED
- 2) MATERIAL: LEXAN F6006, BLACK No. 701, 0.093" THICK  
(REF DART SPEC MLEXS.093-F6006-02)
- 3) FINISH: NONE
- 4) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) UNITS: INCHES UNLESS OTHERWISE NOTED
- 6) BREAK SHARP EDGES: 0.010 MAX
- 7) IDENTIFICATION: IDENTIFY WITH DART P/N "D3281-1" AND BATCH NUMBER "BXXXXX" ON SMOOTH SIDE OF PART USING VIBRATING STYLUS
- 8) WEIGHT: 0.95 lb

D	THICKNESS 0.093 WAS 0.125, MIN THICKNESS 0.070 WAS 0.080, P/N AND B/N ID WITH VIBRATING STYLUS (ZN A7-1, A7-2, A7-3, A7-4); D3281-4 NOW ON PAGE 4; CORRECT WEIGHTS (ZN A8-1, A8-2, A8-3, A8-4)	PH	08.03.28
C	UPDATE DIMS TO MATCH PARTS: COLOUR 701 WAS 700; GENERAL UPDATE	LE	07.10.09
B	NOW LEXAN; DIMS AS MANUFACTURED	CP	05.11.25
A	NEW ISSUE	CP	04.05.03
REV.	DESCRIPTION	BY	DATE
DESIGN	4P		
DRAWN	PH		
CHECKED	5		
MFG. APPR.	5		
APPROVED	5		
DE APPR.	5		
DATE	08.03.28		
<b>DART AEROSPACE LTD</b> HAWKESBURY, ONTARIO, CANADA			
DRAWING NO. D3281		REV. D	SHEET 1 OF 4
TITLE FLOOR PROTECTOR		SCALE	NTS
COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE UNDERSTANDING THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			

SHOP COPY  
 RETURN TO  
 ENGINEERING  
 UNCONTROLLED COPY  
 SUBJECT TO AMENDMENT  
 WITHOUT NOTICE  
 NO 100710






### D3281-2 FLOOR PROTECTOR

#### D3281-2 NOTES:

- 1) THERMOFORM WITH MOLD D3281-2T1 PER DART QSI 022; TRIM AS SHOWN  
MINIMUM THICKNESS AFTER FORMING: 0.070" EXCEPT WHERE INDICATED
- 2) MATERIAL: LEXAN F6006, BLACK No. 701, 0.093" THICK  
(REF DART SPEC MLEXS.093-F6006-02)
- 3) FINISH: NONE
- 4) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) UNITS: INCHES UNLESS OTHERWISE NOTED
- 6) BREAK SHARP EDGES: 0.010 MAX
- 7) IDENTIFICATION: IDENTIFY WITH DART P/N "D3281-2" AND BATCH NUMBER "BXXXXX" ON SMOOTH SIDE OF PART USING VIBRATING STYLUS
- 8) WEIGHT: 0.97 lb

**DART AEROSPACE LTD**  
HAWKESBURY, ONTARIO, CANADA

DESIGN	99	<b>DART AEROSPACE LTD</b>	
DRAWN	99	<b>HAWKESBURY, ONTARIO, CANADA</b>	
CHECKED		DRAWING NO.	REV. D
MFG. APPR.		D3281	SHEET 2 OF 4
APPROVED		TITLE	SCALE
DE APPR.		FLOOR PROTECTOR	NTS
DATE	08.03.28	COPYRIGHT © 2004 BY DART AEROSPACE LTD	
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			



**D3281-3 FLOOR PROTECTOR**

**D3281-3 NOTES:**

- 1) THERMOFORM WITH MOLD D3281-3T1 PER DART QSI 022; TRIM AS SHOWN  
MINIMUM THICKNESS AFTER FORMING: 0.070" EXCEPT WHERE INDICATED
- 2) MATERIAL: LEXAN F6006, BLACK No. 701, 0.093" THICK  
(REF DART SPEC MLEXS.093-F6006-02)
- 3) FINISH: NONE
- 4) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) UNITS: INCHES UNLESS OTHERWISE NOTED
- 6) BREAK SHARP EDGES: 0.010 MAX
- 7) IDENTIFICATION: IDENTIFY WITH DART P/N "D3281-3" AND BATCH NUMBER "BXXXXX" ON SMOOTH SIDE OF PART USING VIBRATING STYLUS
- 8) WEIGHT: 0.87 lb






RELEASED  
08-04-11 MJD

DESIGN	42	<b>DART AEROSPACE LTD</b>	
DRAWN	RF	HAWKESBURY, ONTARIO, CANADA	
CHECKED	3	DRAWING NO.	REV. D
MFG. APPR.	MD	D3281	SHEET 3 OF 4
APPROVED	WJ	TITLE	SCALE
DE APPR.	WJ	FLOOR PROTECTOR	NTS
DATE	08.03.28	<small>COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD</small>	

SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE





**D3281-4 FLOOR PROTECTOR**

NO. 468716  
 WORK ORDER  
 WITHOUT NOTICE  
 SUBJECT TO AMENDMENT  
 UNCONTROLLED COPY  
 ENGINEERING  
 RETURN TO  
 SHOP COPY

**D3281-4 NOTES:**

- 1) THERMOFORM WITH MOLD D3281-4T1 PER DART QSI 022; TRIM AS SHOWN  
 MINIMUM THICKNESS AFTER FORMING: 0.070" EXCEPT WHERE INDICATED
- 2) MATERIAL: LEXAN F6006, BLACK No. 701, 0.093" THICK  
 (REF DART SPEC MLEXS.093-F6006-02)
- 3) FINISH: NONE
- 4) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 5) UNITS: INCHES UNLESS OTHERWISE NOTED
- 6) BREAK SHARP EDGES: 0.010 MAX
- 7) IDENTIFICATION: IDENTIFY WITH DART P/N "D3281-4" AND BATCH NUMBER "BXXXXX" ON SMOOTH SIDE OF PART USING VIBRATING STYLUS
- 8) WEIGHT: 0.87 lb



RELEASED  
 08-04-11 MJD

DESIGN		<b>DART AEROSPACE LTD</b>	
DRAWN		HAWKESBURY, ONTARIO, CANADA	
CHECKED		DRAWING NO.	REV. D
MFG. APPR.		D3281	SHEET 4 OF 4
APPROVED		TITLE	SCALE
DE APPR.		FLOOR PROTECTOR	NTS
DATE	08.03.28	COPYRIGHT © 2004 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD	